

NOTES

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED AND ARE TO BE CHECKED PRIOR TO COMMENCEMENT OF FABRICATION.
2. ALL DIMENSIONS, LEVELS AND ANGLES ARE APPROXIMATE. THE INSTALLATION CONTRACTOR IS RESPONSIBLE FOR CHECKING AND CONFIRMING ALL INDICATED DIMENSIONS, LEVELS AND ANGLES, AND DETERMINING THE POSITION OF ALL SITE WELDS.
3. THIS DRAWING MUST NOT BE SCALED FOR FABRICATION PURPOSES.
4. EXISTING SITE PIPEWORK, EQUIPMENT, CABLES, DUCTS AND BUILDINGS WHERE SHOWN ARE FROM EXISTING RECORDS AS PROVIDED BY NORTHERN GAS NETWORKS LTD. INSTALLATION CONTRACTOR TO LOCATE AND CONFIRM ANY EXISTING SERVICES AND EQUIPMENT PRIOR TO CONSTRUCTION. NORTHERN GAS NETWORKS LTD TO BE INFORMED IMMEDIATELY WHERE THE CURRENT RECORD OF EXISTING SERVICES OR EQUIPMENT IS FOUND TO BE INCORRECT.
5. ALL CIVIL MATERIALS TO BE SUPPLIED BY INSTALLATION CONTRACTOR.
ALL AREAS DISTURBED BY WORKS ARE TO BE MADE GOOD BY THE INSTALLATION CONTRACTOR TO THE SATISFACTION OF NORTHERN GAS NETWORKS LTD. SITE TO BE FINISHED WITH 70mm DEEP CHIPPINGS.
7. HIGH PRESSURE DESIGN AND CONSTRUCTION TO BE IN ACCORDANCE WITH IGM/DT/13 E42 AND NORTHERN GAS NETWORKS LTD SPECIFICATIONS NGN/SP/E/28, NGN/SP/PW/11 AND NGN/SP/TR/18.
8. ALL PIPEWORK AND EQUIPMENT FOR DESIGN PRESSURES ABOVE 7 BARG SHALL BE CONSTRUCTED IN ACCORDANCE WITH SPECIFICATION NGN/SP/PW/11, WELDED AND INSPECTED IN ACCORDANCE WITH NGN/SP/P/2 AND TESTED IN ACCORDANCE WITH NGN/SP/PT/1. ANY DEVIATION FROM THESE SPECIFICATIONS SHALL BE AGREED IN ADVANCE IN WRITING WITH NORTHERN GAS NETWORKS LTD.
9. ALL PIPEWORK AND EQUIPMENT FOR DESIGN PRESSURES 7 BARG AND BELOW TO BE CONSTRUCTED AND TESTED IN ACCORDANCE WITH SPECIFICATION NGN/PM/MS/1 AND ITS MODULES, AND WELDED IN ACCORDANCE WITH NGN/SP/P/1. ANY DEVIATION FROM THESE SPECIFICATIONS SHALL BE AGREED IN ADVANCE IN WRITING WITH NORTHERN GAS NETWORKS LTD.
10. ALL PIPEWORK TO BE THOROUGHLY CLEANED INTERNALLY AND EXTERNALLY BEFORE COMMISSIONING.
11. ALL PIPEWORK SITUATED ABOVE GROUND TO BE EXTERNALLY PAINTED IN ACCORDANCE WITH NGN/SP/PA/10.
12. SUITABLE TEMPORARY SUPPORTS SHOULD BE INSTALLED WHERE REQUIRED. CONTRACTOR TO SUPPLY ALL TEMPORARY SUPPORTS.
13. ALL LIFTING OPERATIONS TO BE AGREED IN ADVANCE WITH NORTHERN GAS NETWORKS LTD.

© THE INFORMATION CONTAINED HEREIN IS CONFIDENTIAL AND IS THE COPYRIGHT OF RUSH CONSTRUCTION SERVICES AND ITS CLIENT. IT MUST NOT BE COPIED OR REPRODUCED IN ANY FORM FOR THE TRANSMISSION TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF RUSH CONSTRUCTION SERVICES OR ITS CLIENT.

REV	DESCRIPTION	DRN	CHK	APP	DATE
G	ISSUED FOR APPRAISAL	RCS	WP	TI	00/11/13
F	ADDED PATHS & DUCTING	RCS	WP	TI	23/09/13
E	UPDATED FROM SITE SURVEY	RCS	WP	TI	05/09/13
D	ISSUED FOR HAZOP	RCS	WP	TI	03/07/13
C	PRE-HEAT DETAIL ADDED	RCS	WP	TI	01/07/13
B	METER STREAM REVISED	RCS	WP	TI	10/06/13
A	PRELIMINARY ISSUE	RCS	WP	TI	10/06/13



4 The Old Mill
Mill Road
Okehampton
Devon
EX20 1PR
Tel: 01837 658515

CLIENT
NORTHERN GAS NETWORKS LTD

PROJECT
WETHERAL PRI

TITLE
PROPOSED SITE LAYOUT

SCALE
1:200 @ A1

DRAWING NO.
RCS-2010185-WETH-P-006

REV
G

